

Awarded 7/6/2015

Gary Anderson Home Improvement, LLC
46 Gile Road, Nottingham, NH 03290

Date: November 17, 2014

Proposal/Contract #: 111714

Contract Sales Coordinator: *Gary A. Anderson*

Customer Information:

Town of Deerfield
Box 159
8 Raymond Road
Deerfield, NH 03037

Job Location:

Deerfield Town Hall
George B. White Building
Deerfield, NH

Attn: Mark Tibbetts 48c1@metrocast.net

Telephone Number:

Rear Field Side Entranceway to Far Corner

1. Strip existing steel siding and prep for new to rear corner.
2. Provide Demilec Heat Lock Plus – 200 3 inch foam insulation all wall areas.
3. ½” Zipwall sheathing, tape all seams.
4. Remove double door entrance with side lite and replace with similar. (white)
5. Remove five single entrance doors and replace with similar.
6. Remove existing picture window units and replace with double Andersen units Model # -----.
7. Install board and batten vinyl siding on existing wooden awning areas as well as all soffit and fascia as needed.
8. Install double 4” vinyl siding to rear corner with accessories. (To be supplied by the Town of Deerfield.)
9. Spray paint fascia white.

\$40,050.00

Proposal

E. Guimond Construction LLC

103 Knox Road

Bow, NH 03304

603-224-8367

eguimondlc@comcast.net

Town of Deerfield Replace Windows at GBW Building

June 29th, 2015 5:00pm

We are submitting a price to remove the old rotten exterior wall sheathing and windows and doors on the parks and recreation building and the back side of the existing George B. White town office building. The price includes these other modifications that are listed below.

1. We will remove the old existing steel siding, approximately 135' lineal feet that is on the back of the building and dispose of it.
2. We will provide and install 3" spray foam insulation into the interior stripped siding wall areas.
3. We will install ½" zip wall sheathing and tape all the seams on these wall areas.
4. We will remove and replace five single entrance doors and replace them with similar metal insulated ½ glass 3' x 6' x 8" doors with panic hardware and door closures.
5. We will remove the existing double door and replace it similar white metal insulated ½ glass door with panic hardware and door closures with a glass side light.
6. We will remove four existing picture window units and replace them with sizes and specifications that have been provided by Mark Tibbetts and the Town of Deerfield.
7. We will remove and replace one rear window with an Anderson window unit from the size and specifications that were provided Mark Tibbetts and the Town of Deerfield.
8. We will repaint the existing rake trim with white exterior paint.
9. We will install new board and batten vinyl siding on the existing wooden awning areas as well as on all the soffit and fascia areas as needed.
10. We will install double 4" vinyl siding and accessories on approximately 135' lineal feet of exterior walls on the parks and recreation and tennis court sides of the building. The vinyl siding and trim are to be supplied by the town of Deerfield.
11. We will remove and clean up all debris from the premises into dumpster supplied by the town.
12. All electrical work and or plumbing and mechanical work needed to complete this project is to be supplied by the town of Deerfield.

Our proposal price is \$63,395.00 (sixty three thousand three hundred ninety five dollars)

Ernest Guimond



June 29, 2015



ESTIMATE

Nazar Lopushansky
 3 SANBORN RD, SUITE #3
 LONDONDERRY, NH 03053
 www.ScoreConstruction.us
 (603) 260-5494
 (603) 440-3967 Cell
 nazar.scoreconstruction@gmail.com

TO:
 Town of Deerfield
 Selectmen Office
 8 Raymond Road
 Deerfield, NH
 GBW Building

JOB DESCRIPTION
Renovations

	AMOUNT
Strip Existing Metal Siding 34 sq	\$ 8,500.00
Frame-in wall openings and sheetrock interior, trim windows	\$ 9,000.00
2x4 Spray Insulation 22sq	\$ 9,250.00
1/2" Zipwall sheathing 34 SQ - 102 sheets	\$ 6,988.00
Storefront - replace with new (double door and 4' side window) installed	\$ 5,500.00
5- 36" steel doors with all hardware panic and push bars, 1/2 light	\$ 6,000.00
5 steel doors install	\$ 2,500.00
Install vertical siding materials and labor (assuming materials are not higher then normal)	\$ 6,000.00
Install horizontal siding labor 22sq	\$ 8,250.00
Paint rake	\$ 2,650.00
Install windows	\$ 1,125.00
Windows	\$ 4,000.00
Mobilization:	\$ 225.00
Disposal Fee:	\$ 1,600.00
Remove and dispose of all debris	
TOTAL ESTIMATED JOB COST	\$ 71,588.00

All work and material is guaranteed to be as specified. Any alteration or deviation from above specifications involving extra costs will be executed only upon written orders and will become an extra charge over and above the estimate.
 Overdue accounts subject to a service charge of 15% per month.
 Deposit for this work will be required for mobilization and purchase of all materials.

Nazar Lopushansky

 PREPARED BY

6/29/2015
 DATE

ACCEPTED BY

DATE